

TIN No.33431883304

CST No.728473 Dt. 12-04-2005

NEUROTRONIX SYSTEMS INDIA PVT. LTD.



Date: 15.09.2012

To

**The Commissioner ,
Villiyannur commune panchayat,
Villiyannur,
Pondicherry.**

Respected Sir,

Sub:Quotation for New signal Errection at pathukannu junction -Reg

We enclose herewith our lowest quotation for new signal erection at Pondiherry, Villiyannur PATHUKANNU junction.


We request you to kindly approve the same & issue the work order at an early date.

Thanking and assuring the best of our service always,

We remain,

Yours truly,

For Neurotronix Systems India Pvt Ltd,.


Authorized Signatory

Encl:

Quotation



NEUROTRONIX SYSTEMS INDIA PVT. LTD.

To:
The Commissioner,
Villiyannur commune panchayat
Villiyannur
Pondicherry

Date:15.09.12

Sir,
Sub: Proforma Invoice for Pathukannu Junction - reg.

QUOTATION

SL.No	Description	Qty	Unit	Rate/Qty	Amount in Rs.
1	Supply and erection of 20' height T pole made by class B MS pipe 5" dia, 4mmtk with MS base plate of size 1.5'x1.5' of 16mmtk including embedding below ground level of 1 mt depth with CC 1:2:4 of 75cm x 75cm x100cm, painted with yellow enameled two coat over one coat of zinc chomate primer as directed etc complete.	3	No	20000.00	60000.00
2	Supply and erection of 20' height L pole made by class B MS pipe 5" dia, 4mmtk with MS base plate of size 1.5'x1.5' of 16mmtk including embedding below ground level of 1 mt depth with CC 1:2:4 of 75cm x 75cm x100cm, painted with yellow enameled two coat over one coat of zinc chomate primer as directed etc complete.	5	No	18000.00	90000.00
3	supplying and fixing of signal doom made by water proof fiber material of size 1'x1' with 60- 130 nos LED light of required colour for supply voltage of AC 230 +-or- 10% and supply from doom 17volt DC voltage of red, yellow, green colours to working the voltage variation from 300 volt to 160 volt and wattage with power SMPS AC to DC converter fixing with existing pole using necessary clamp arrangements firmly etc comple.	68	No	6000.00	408000.00
4	Supply and Laying of 14 Core Cable of 0.75 Sq.mm copper U.G cables - 1.1 KV grade (Make -Orbit/Finolex)	150	1rmt	230.00	34500.00
5	Supply and laying of 6 core cables of 0.75 Sq.mm Copper U.G Cables - 1.1 KV grade (Make -Orbit/Finolex)	150	1rmt	130.00	19500.00
6	Supply and laying of 1.0 Sq.mm ISI marked, FR PVC insulated, single core Copper conductor Cables. (Make -Orbit/Finolex)	180	1rmt	11.00	1980.00
7	Supply and laying of 6 core cables of 1 Sq.mm. PVC coated Copper O.H Cables 1.1 KV grade (Make -Orbit/Finolex)	180	1rmt	49.00	8820.00
8	providing and fixing 2.5 inch pvc HD pipe for UG cable duct.	150	1rmt	350.00	52500.00
9	Supply and fixing 20mm dia spring hose of black and green colour of heavy duty etc complete to covering to OH cable found wherever necessary.	50	1rmt	20.00	1000.00
10	Supply and fixing and commissioning of control box unit made with metal sheet of size 600mm x 750mm x 450cm fitted with processor of brand Atmel AT89c52 LED interface, keyboard interface for 5 way junction with traic type switching with provisions like on sight programming facility, pedestrian handling. automatic on/off system and this system would be upgraded with UPS backup option and solar backup with auto/ manual / manual flash option. the control unit having 1 year warranty etc comple.	1	No	35000.00	35000.00
11	Supply and fixing of digital LED timer of size 21/2' x 21/2' with red and green LED arrangement with three transformer 22volt 1no and 6volt of 2nos and timer PCB fixed with existing pipe pole using necessary clamp etc comple.	6	No	19300.00	115800.00

TIN No.33431883304


CST No.728473 Dt. 12-04-2005


NEUROTRONIX SYSTEMS INDIA PVT. LTD.



12	Supply and fixing of connector box of metal material with connector pin arrangements and fixed with necessary clamp with existing pipe etc comple.	7	No	1400.00	9800.00
13	Supply and fixing of doom set accessories (post clamp, hose clip)	34	No	238.00	8092.00
14	Fabrication , supply, ertion testing and commissioning of one no metering panel board for the power supply of our all size 600 mmx450mmx300mm made out of 16SWG thick cold rolled M.S sheet. The compartment have energy meter viewing class with 8mm hylem sheet including 32 amps fuse -one no, 32 amps neutral link , main switch 32amps (kundan/standard) , including service U.G cable 2x16 sq mm (aluminium) from EB post anywhere near by up to panel board. interior connection between the switch fuse units are to be done with 2.5sq.mm ISI market FR PVC insulated single core copper conductor cable (make finolex/kundan). the door should be flush type inter locking in one position. the panel board with sufficient holes of required diameter. the panel should be painted with two coats rust proof Zinc chromate and two coats of anti corrosive epoxy shade grey paint after completion of derusting process. the panel board should be formal fixed with excising pole using necessary clamp B27 arrangements or in earth with adequate clearance from ground using CC 1:2:4 as directed by the engineer in charge.	1	No	12620.00	12620.00
15	Supply and fixing of cat's eye red and yellow colour on stop line.	300	No	350.00	105000.00
16	Supply and painting of Stop line road marking white Paint	20	ltr	450.00	9000.00
17	Supply and pasting of RED reflecting stickers on the signal pole	50	1rmt	50.00	2500.00
18	supplying and fixing UG cable embedding below ground level of 2' depth with CC 1:2:4.	134	1rmt	150.00	20100.00
				Grand Total	994212.00

For Neurotronix Systems India Pvt Ltd.,


Authorized signature



NEUROTRONIX SYSTEM INDIA (P) LTD.
 Chennai - 600 024

Issued By

Approved By

Pondicherry

Villianur

Thirukanur

Selipettu

durapet

**PATHUKANNU
 JUNCTION**

EB Post

CANTILEVER POLE

CONTROL UNIT

METER BOX

UG CABLE

SIGNAL LIGHTS

Green

Red

Yellow

